

STANDARD SILT CONTROL NOTE:

1. THE PERMITTEE SHALL NOTIFY THE CITY ENGINEER'S OFFICE 24-HOURS IN ADVANCE OF CONDUCTING INITIAL LAND-DISTURBING ACTIVITIES IN ACCORDANCE WITH PADUCAH ORDINANCE CH. 50 ART. IV 50-178 (C).
2. APPLICABLE EROSION CONTROL DEVICES/MEASURES SHALL BE PERPETUALLY MAINTAINED AND CONTROLLED WITHIN THE DEVELOPMENT SITE IN ACCORDANCE WITH THE APPROVED EPSC PLAN. APPLICABLE EROSION CONTROL DEVICES/MEASURES SHALL BE INSTALLED PRIOR TO STRIPPING OF TOPSOIL AND VEGETATIVE COVER AND PERPETUALLY MAINTAINED DURING THE CONSTRUCTION PHASE OF THIS PROJECT UNTIL A PROPER VEGETATIVE GROUND COVER IS ESTABLISHED. IF THIS IS IGNORED, THE PROJECT WILL BE SUBJECT TO BEING SHUT DOWN IMMEDIATELY WITHOUT NOTICE. THE PROJECT WILL NOT RESUME UNTIL PROPER SILT PROTECTION HAS BEEN INSTALLED AND APPROVED BY THE CITY ENGINEER'S OFFICE. THE GENERAL CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR ALL COSTS ASSOCIATED WITH ANY CLEANUP/RESTORATIONS, BUT NOT LIMITED TO ADJACENT DITCHES, CREEKS, STREAMS, PROPERTIES, AND APPLICABLE FINES DIRECT AND/OR INDIRECT SHOULD DISPLACEMENT OF SILT BEYOND THE DEVELOPMENT SITE OCCUR.
3. ALL POTENTIAL EROSION SHALL BE CONTROLLED IN SUCH A MANNER SO AS TO PREVENT ANY DISPLACEMENT OF SILT TO THE ADJACENT PROPERTY OWNERS, STREAMS, AND/OR RIGHT OF WAY. THIS CONTROL SHALL BE IMPLEMENTED ACCORDING TO THE GUIDELINES ESTABLISHED ON THIS PLAN AND SHALL BE MAINTAINED THROUGHOUT CONSTRUCTION AND UNTIL PROPER GROUND COVER HAS BEEN ESTABLISHED.
4. QUALIFIED PERSONNEL OF THE PERMITTEE SHALL INSPECT ALL STORM WATER CONTROL MEASURES, DISCHARGE LOCATIONS, VEHICLE EXITS, DISTURBED AREAS OF THE CONSTRUCTION SITE AND MATERIAL STORAGE AREAS AT LEAST ONCE EVERY SEVEN (7) DAYS AND WITHIN 24 HOURS OF THE END OF A STORM THAT IS 0.5 INCHES OR GREATER AND AREAS THAT HAVE BEEN TEMPORARILY OR FINALLY STABILIZED AT LEAST ONCE A MONTH. INSPECTIONS BY THE CITY OF PADUCAH'S ENGINEERING DEPARTMENT DOES NOT EXEMPT THE PERMITTEE FROM MAKING WEEKLY INSPECTIONS OR INSPECTIONS 24 HOURS AT THE END OF A STORM EVENT THAT IS 0.5 INCHES OR GREATER.
5. A NOTICE OF TERMINATION (NOT) SHALL BE FILED WITH THE CITY ENGINEER'S OFFICE AND THE KENTUCKY DIVISION OF WATER WHEN ALL PERMIT REQUIREMENTS HAVE BEEN COMPLETED, FINAL STABILIZATION HAS BEEN ACHIEVED, AND THEIR FACILITIES NO LONGER HAVE ANY STORM WATER DISCHARGES. THE NOT CAN ALSO BE FILED IF ANOTHER PARTY HAS ASSUMED CONTROL OVER A PORTION OR ALL AREAS OF THE SITE PREVIOUSLY PERMITTED AND NEW PERMITS HAVE BEEN ISSUED TO THE PARTY ASSUMING CONTROL. THE CITY ENGINEER'S OFFICE WILL COMPLETE A FINAL INSPECTION OF THE SITE AND MAY RELEASE THE SURETY IN FULL OR GRANT A PARTIAL RELEASE (NOT ATTACHED).